|             | <b>Test</b><br>Air permeability and watertightness of<br>installation foam  |
|-------------|---|
|             | Test Report 10-001777-PR01<br>(PB-K05-02-en-01)   |
| Client      | Henkel AG & Co. KG<br>Henkelstraße 67   |
|             | D-40589 Düsseldorf<br>Germany   |
|             |   |
| Product     | Installation foam (in-situ foam)  |
| Designation | 1K-PU Pistolenschaum Teroson TS 537 (gunned foam)   |
| Dimensions  | Joint cross section 20 mm x 60 mm   |
| Material    | One-component, moisture curing PU-based installation foam   |
|             | The air permeability of the installation foam was deter-<br>mined for an "ideal" joint and in new condition on the basis<br>of DIN 18542, Clause 7.2. The results cannot be used to |

demonstrate air tightness and watertightness of connecting joints between building components (gunned with foam) in practical end-use applications. Special features

Results Air permeability in new condition  $a < 0.1 \text{ m}^3 / [h \cdot m \cdot (daPa)^{2/3}]$ 

> Watertightness in new condition No water penetration at up to 750 Pa

ift Rosenheim 08 June 2011

Wolfgang Jehl, Dill.-Ing. (FH) Assistant Head of Testing Department Building Materials & Semi-Finished Products

Thomas Stefan, Dipl.-Ing. (FH) **Test Engineer** Tightness & Wind Load

Sitz: 83026 Rosenheim AG Traunstein, HRB 14763 Sparkasse Rosenheim Kto. 3822 BLZ 711 500 00

ROSENHEIM

**Basis** Test based on DIN 18542:1999-01 \*), Sealing of outside wall joints with impregnated sealing tapes made of cellular plastics, Clause 7.2, Air permeability \*)

Test standard/s: EN 12114 : 2000-03 EN 1027 : 2000-06

\*) see explanations in test report

**Representation of test** specimen



Instructions for use

This test report serves to demonstrate the above material property

#### Validity

The data and results given relate solely to the tested and described specimen.

The effects of weathering and ageing have not been covered.

#### Notes on publication

The ift Guidance Sheet "Conditions and Guidance for the Use of ift test reports" applies.

The cover sheet can be used as an abstract.

#### Contents

The report comprises a total of 6 pages.

- Object 1
- 2 Procedure
- 3 Results





ift Rosenheim GmbH



Theodor-Gietl-Str. 7 - 9 D-83026 Rosenheim Tel.: +49 (0)8031/261-0 Fax: +49 (0)8031/261-290 www.ift-rosenheim.de



# 1 Object

## 1.1 Description of test specimen

The description is based on inspection of the test specimen at **ift** Rosenheim. Item designations/numbers as well as material specifications were given by the original client.

| Product designation  | 1K-PU Pistolenschaum Teroson TS 537 (gunned foam)   |
|----------------------|---|
| Material / Base      | one-component, moisture curing PU-based installation foam (in-<br>situ foam), colour: white |
| Weight per unit area | 18 kg/m <sup>3</sup>  |
| Cell structure       | fine to medium sized pores, mainly closed pores   |

For more technical details refer to the Technical Sheet of the client

For testing, the installation foam was gunned into a test apparatus composed of square aluminium tubes. The test was based on DIN 18542, Clause 7.2 and Fig. 1, test specimen for air permeability test of linear joints. Spacer discs inserted between the square tubes ensured uniform joint width of 20 mm. Joint depth was 60 mm.

3 joints of each 1,000 mm joint length were produced for the test. After the time specified by the manufacturer to achieve full loading capacity, the installation foam squeezed out from the joint was cut off on both sides flush with the joint.

## 1.2 Representation of test specimen

The photographs were taken at the **ift** during testing.



Fig. 1 Joints gunned with foam in test apparatus for linear joints according to DIN 18542, mounted in window test rig

Test: Air permeability and watertightness of installation foam Page 3 of 6 Test report 10-001777-PR01 (PB-K05-02-en-01), dated 08 June 2011 Client Henkel AG & Co. KGaA, D-40589 Düsseldorf



## 2 Procedure

### 2.1 Sampling

The samples were selected by the original client.

| Delivered on | 8 February 2011 by the original client. |
|--------------|---|
|--------------|---|

Preparation The installation foam was gunned by the staff of the testing body into the test apparatus on 08 February 2011. Prior to gunning the foam, the test apparatus and the cans containing the foam were conditioned at standard atmosphere (23 C, 50 % rel. humidity) for at least 1 week. During gunning the installation foam, the joint faces and the foam surfaces were wetted with water sprayed from a spray bottle. Prior to the test, the test device including the foamed joints were stored at standard atmosphere for at least one week.

### 2.2 Method/s

### Basis

| DIN 18 542 : 1999-01  | Sealing of outside wall joints with impregnated sealing tapes<br>made of cellular plastics - Impregnated sealing tapes - Re-<br>quirements and testing (subtest as per Clause 7.2) |  |  |  |  |
|-----------------------|--|--|--|--|--|
|                       | Since there is no comparable standard known for the objective<br>of testing this installation foam, the test set-up was based on<br>this standard.                                 |  |  |  |  |
| EN 12114 : 2000-03 *) | Thermal performances of buildings - Air permeability of building components and building elements - Laboratory test method   |  |  |  |  |
| EN 1027 : 2000-06     | Windows and doors - Watertightness - Test method   |  |  |  |  |
| Boundary conditions   | as per standard specifications   |  |  |  |  |

### 2.3 Measuring and test equipment

Window test rig Device No.: 22200

## 2.4 Testing

| Date/Period       | 30 March 2011                |
|-------------------|------------------------------|
| Testing personnel | Thomas Stefan, DiplIng. (FH) |

Test: Air permeability and watertightness of installation foam Page 4 of 6 Test report 10-001777-PR01 (PB-K05-02-en-01), dated 08 June 2011 Client Henkel AG & Co. KGaA, D-40589 Düsseldorf



## 2.5 Test sequence

#### 2.5.1 Air permeability test

Fig, 1 below plots the test sequence (pressure steps) according to EN 12114 to determine air permeability.





Fig. 1 Test sequence (pressure steps)

Leakages of the test set-up were determined by comparative measurement (zero measurement) during which the joints to be tested were masked air-tight and recorded. These leakages were then taken into account for the subsequent air permeability test of the joints. Thus only the air flow through the tested in-situ foamed joints was determined.

### 2.5.2 Watertightness test

The test is based on DIN EN 1027 using a water flow rate of approx. 2 l/(min m<sup>2</sup>) (Fig. 2).



Test: Air permeability and watertightness of installation foam Page 5 of 6 Test report 10-001777-PR01 (PB-K05-02-en-01), dated 08 June 2011 Client Henkel AG & Co. KGaA, D-40589 Düsseldorf



## 3 Results


## 3.1 Air permeability test in new condition

The measured results are used to determine linear air permeability  $[m^3/(hm)]$  up to a test pressure difference of 1,000 Pa. Table 1 lists the values. Diagram 1 shows the plotted values. Diagram 1 shows also, for orientation, the requirements for evaluation of air permeability of linear joints as per DIN 4108, Part 2, expressed by the joint permeability coefficient a where a < 0.1 m<sup>3</sup> / [h m (daPa)<sup>2/3</sup>].

 Table 1
 Results of air permeability test

| Pressure steps | Ра    | 50 | 73 | 106 | 154   | 225   | 325   | 473   | 688   | 1,000 |
|----------------|-------|----|----|-----|-------|-------|-------|-------|-------|-------|
| Air flow       | m³/h  |    | *) |     | 0.01  | 0.01  | 0.01  | 0.01  | 0.02  | 0.02  |
|                | m³/hm |    | *) |     | 0.002 | 0.002 | 0.003 | 0.004 | 0.005 | 0.005 |

\*) No measurable air flow. Measuring accuracy of test setup was 0.01 m<sup>3</sup>/h.



**Diagram 1** Linear air permeability of installation foam for an "ideal" joint of 20 mm x 60 mm cross section.

Test: Air permeability and watertightness of installation foam Page 6 of 6 Test report 10-001777-PR01 (PB-K05-02-en-01), dated 08 June 2011 Client Henkel AG & Co. KGaA, D-40589 Düsseldorf



## 3.2 Watertightness test in new condition

When testing for watertightness,

### no water penetration up to 750 Pa

through the foamed joints was detected.

The results were obtained from measurement in new condition with uniform joint widths and smooth as well as parallel joint faces, i.e. for an "ideal" joint. The effects and changes resulting from weathering and/or ageing, different nature of the joint faces and any joint movements, have not been taken into account. Thus the results cannot be used for any connecting joints (gunned with foam) in practical end use applications.

ift Rosenheim 08 June 2011